

**CLOSURE PLAN
NAVAL TRAINING CENTER LANDFILL
SAN DIEGO, CALIFORNIA**

PREPARED FOR:

San Diego County Regional Airport Authority
P.O. Box 82776
San Diego, California 92138-2776

PREPARED BY:

Ninyo & Moore Geotechnical and Environmental Sciences Consultants
5710 Ruffin Road
San Diego, California 92123

March 1, 2007
Project No. 105111023

March 1, 2007
Project No. 105111023

Mr. Richard Gilb
Manager Environmental Affairs
San Diego County Regional Airport Authority
P.O. Box 82776
San Diego, California 921138

Subject: Closure Plan
Naval Training Center Landfill
San Diego, California


Dear Mr. Gilb:

In general accordance with your request, we have prepared this Closure Plan to obtain regulatory approval for closure of the former Naval Training Center Landfill. As indicated by the San Diego County Regional Airport Authority, the primary goal of this project is to remove the buried wastes and backfill the excavation with suitable materials to support the future site use for airport operations. A secondary goal of the project is to implement the closure activities in a manner that may satisfy requirements for clean closure of the landfill in accordance with applicable sections of Title 27 California Code of Regulations (CCR). This closure plan has been prepared in general accordance with applicable requirements for "clean closure plans" as indicated in Title 27 CCR Section 21810.


This closure plan provides information on the types and extent of the buried wastes subject to removal, recommends site cleanup criteria to satisfy clean closure requirements, and describes the proposed procedures and record-keeping to be implemented during closure activities. Following closure of the landfill, the Airport Authority plans to develop the site with airport facilities, which may include aircraft apron, airport terminal buildings, roadway, and parking facilities.

We appreciate the opportunity to provide continued services on this important project.

Sincerely,
NINYO & MOORE


Sree Gopinath, P.E.
Principal Engineer




Beth S. Abramson-Beck
Principal Geologist



SKG/BAB/kmf

Distribution: (2) Addressee

- (1) Mr. John Odermatt, California Regional Water Quality Control Board, 9174 Sky Park Court, Suite 100, San Diego, California 92123
- (1) Mr. Brian McDaniel, California Regional Water Quality Control Board, 9174 Sky Park Court, Suite 100, San Diego, California 92123
- (2) Mr. Bill Prinz, The City of San Diego, Solid Waste Local Enforcement Agency, 1010 Second Avenue, Suite 600, MS 606L San Diego, California 92101-4998
- (1) San Diego Air Pollution Control District, 10124 Old Grove Road, San Diego, California 92131

TABLE OF CONTENTS

	<u>Page</u>
EXECUTIVE SUMMARY	1
1. INTRODUCTION	1
1.1. PROJECT OBJECTIVES	2
1.2. SCOPE OF WORK	3
1.3. REPORT ORGANIZATION	5
2. REGULATORY FRAMEWORK	7
2.1. TITLE 27 CCR SECTION 20950	7
2.2. TITLE 27 CCR SECTION 21090	7
2.3. TITLE 27 CCR SECTION 21810	8
2.4. PROPOSED CLOSURE METHOD	10
2.5. CLEANUP LEVELS	11
2.6. AGENCY REVIEW OF CLEAN CLOSURE PLAN	12
2.7. CONFIRMATION OF CLEAN CLOSURE	13
2.8. POST-CLOSURE MAINTENANCE AND LAND USE	13
2.9. ANTICIPATED WASTE STREAMS	14
2.10. COMMUNITY RELATIONS	15
2.11. CALIFORNIA ENVIRONMENTAL QUALITY ACT	16
3. SITE LOCATION, DESCRIPTION, AND HISTORY	17
3.1. SITE LOCATION	17
3.2. SITE HISTORY AND OPERATIONAL STATUS	17
3.3. BASE REALIGNMENT AND CLOSURE PLAN	22
3.4. SAN DIEGO COUNTY REGIONAL AIRPORT AUTHORITY OWNERSHIP	23
4. REGULATORY HISTORY	23
5. SITE CHARACTERIZATION	26
5.1. PHYSICAL CHARACTERISTICS	27
5.1.1. STRUCTURES AND TOPOGRAPHY	27
5.1.2. REGIONAL GEOLOGIC SETTING	27
5.1.3. SITE SPECIFIC GEOLOGY AND SUBSURFACE CONDITIONS	28
5.1.4. HYDROGEOLOGIC SETTING	30
5.1.5. SITE HYDROGEOLOGY	30
5.1.6. SURFACE WATER HYDROLOGY	31
5.2. NATURE AND EXTENT OF BURIED WASTES	32
5.2.1. LANDFILL EXTENT	32
5.2.2. NATURE OF BURIED WASTE	34
5.2.3. SOILS	37
5.2.4. GROUNDWATER QUALITY	39
5.2.5. LANDFILL GAS MONITORING	39
6. CLEANUP LEVELS	39

6.1.	EVALUATION OF COCS	40
6.2.	BACKGROUND SOIL CONCENTRATIONS	42
6.2.1.	POLYCYCLIC AROMATIC HYDROCARBONS	43
6.2.2.	POLYCHLORINATED BIPHENYLS	44
6.2.3.	DIOXINS/FURANS	45
6.2.4.	ORGANOCHLORINE PESTICIDES	46
6.2.5.	PENTACHLOROPHENOL AND 2,4,5-TRICHLOROPHENOL	46
6.2.6.	TOTAL PETROLEUM HYDROCARBONS	47
6.2.7.	PHTHALATES	48
6.2.8.	METALS.....	48
6.3.	CONTAMINANTS OF CONCERN AND CLEANUP LEVELS	52
7.	EXCAVATION AREA	53
8.	PROJECT CONTROLS	54
8.1.	COMMUNITY HEALTH AND SAFETY	55
8.2.	SITE HEALTH AND SAFETY REQUIREMENTS	55
8.2.1.	WORKER HEALTH AND SAFETY.....	56
8.2.2.	TRAINING REQUIREMENTS	57
8.2.3.	EMERGENCY RESPONSE PLAN	58
8.3.	AIR QUALITY MONITORING.....	58
8.3.1.	AIR QUALITY CONCERNS.....	58
8.3.2.	SITE WORKER AIR MONITORING	59
8.3.3.	GAS AND VAPOR MONITORING.....	59
8.3.4.	AIR MONITORING FOR ODOR NUISANCE.....	59
8.3.5.	SAMPLING METHODS.....	60
8.3.6.	BIRD CONTROL	60
8.4.	RADIATION MONITORING	61
8.5.	NOISE MONITORING.....	61
8.6.	TRAFFIC CONTROL.....	61
8.7.	GENERAL PERMIT FOR STORM WATER DISCHARGES	62
8.7.1.	STORM WATER POLLUTION PREVENTION PLAN.....	62
8.7.2.	AIRPORT SECURITY	63
8.8.	WASTE MANAGEMENT.....	63
8.9.	WORK IMPLEMENTATION PLAN.....	63
8.10.	ENVIRONMENTAL CONSIDERATIONS	64
8.11.	REGULATORY REQUIREMENTS	65
9.	PROJECT MANAGEMENT, RESPONSIBILITY, AND AUTHORITY.....	66
9.1.	PROJECT APPROACH	66
9.2.	PROJECT TEAM	66
9.2.1.	AWARDING AUTHORITY	67
9.2.2.	PROJECT ENGINEER.....	67
9.2.3.	GENERAL CONTRACTOR.....	67
9.2.4.	PROJECT ENVIRONMENTAL CONSULTANT.....	69
9.2.5.	REGULATORY AGENCIES.....	70

Figures

- Figure 1 – Site Location Map
- Figure 2 – Site and Vicinity Map
- Figure 3 – Estimated Extent of Buried Wastes
- Figure 4 – Estimated Extent of Burned Waste in Airport Operational Area
- Figure 5 – Soil and Groundwater Assessment Locations
- Figure 6 – Cross Section A-A'
- Figure 7 – Summary of Zone A Groundwater Analytical Results – Organic Compounds, October 2006
- Figure 8 – Summary of Zone A Groundwater Analytical Results – Metals, October 2006
- Figure 9 – Summary of Zone B Groundwater Analytical Results – Organic Compounds, October 2006
- Figure 10 – Summary of Zone B Groundwater Analytical Results – Metals, October 2006
- Figure 11 – Excavation Area and Sampling Grid
- Figure 12 – Subsurface Utility Map
- Figure 13 – Temporary Facilities Layout

Tables

- Table 1 – Contaminants of Concern and Soil Cleanup Goals

Appendices

- Appendix A – Summary of Previous Site Investigations
 - Table A-1 – Summary of Previous Investigations- NTC Landfill Site
 - Table A-2 – Summary of Burned Waste Analytical Results
 - Table A-3 – Summary of Previous Subsurface and Surface Soil Sample Activities
 - Table A-4 – Summary of Subsurface Soil Sample Analytical Results-Organic Compounds
 - Table A-5 – Summary of Subsurface Soil Sample Analytical Results-Metals and Boron
 - Table A-6 – Summary of Surface Soil Sample Analytical Results-Organic Compounds
 - Table A-7 – Summary of Surface Soil Sample Analytical Results-Metals
 - Table A-8 – Summary of Groundwater Elevation Measurements-Former NTC Landfill Site
 - Table A-9 – Summary of Groundwater Analytical Results-Volatile Organic Compounds
 - Table A-10 – Summary of Groundwater Analytical Results-Semi-Volatile Organic Compounds
 - Table A-11 – Summary of Groundwater Analytical Results-Metals
 - Table A-12 – Summary of Groundwater Quality Results
 - Table A-13 – Summary of Landfill Gas Well Monitoring Results
-
- Figure A-1 – Historical MSW Disposal Area
 - Figure A-2 – Summary of Burned Waste Analytical Results
 - Figure A-3 – Summary of Subsurface Soil Sample Analytical Results-Organic Compounds
 - Figure A-4 – Summary of Subsurface Soil Sample Analytical Results-Metals
 - Figure A-5 – Summary of Surface Soil Sample Analytical Results-Organic Compounds
 - Figure A-6 – Summary of Surface Soil Sample Analytical Results-Metals

- Appendix B – Letters from LEA regarding Imported Soil

Appendix C – Community Health and Safety Plan (CHSP)
Appendix D – Field Sampling and Analysis Plan (FSAP)
Appendix E – Quality Assurance Plan (QAP)
Appendix F – Waste Management Plan (WMP)